



Population dynamics and reproduction strategies of planktonic foraminifera in the open ocean

Julie Meilland¹, Michael Siccha¹, Maike Kaffenberger¹, Jelle Bijma², and Michal Kucera¹

¹MARUM Center for Marine Environmental Sciences, University of Bremen, Leobener Straße 8, 28359 Bremen, Germany

²Alfred Wegener Institute Helmholtz Centre for Polar and Marine Research, Bremerhaven, Germany

Correspondence: Julie Meilland (jmeilland@marum.de)

Received: 28 May 2021 – Discussion started: 9 August 2021

Revised: 4 October 2021 – Accepted: 5 October 2021 – Published: 28 October 2021

Abstract. It has long been assumed that the population dynamics of planktonic foraminifera is characterised by synchronous reproduction associated with ontogenetic vertical migration. However, due to contradictory observations, this concept became controversial, and subsequent studies provided evidence both in favour and against these phenomena. Here we present new observations from replicated vertically resolved profiles of abundance and shell size variation in four species of planktonic foraminifera from the tropical Atlantic to test for the presence, pattern, and extent of synchronised reproduction and ontogenetic vertical migration in this oceanic region. Specimens of *Globigerinita glutinata*, *Globigerinoides ruber ruber*, *Globorotalia menardii* and *Orbulina universa* were collected over the first 700 m resolved at nine depth intervals at nine stations over a period of 14 d. Dead specimens were systematically observed irrespective of the depth interval, sampling day and size. Conversely, specimens in the smaller size fractions dominated the sampled populations at all times and were recorded at all depths, indicating that reproduction might have occurred continuously and throughout the occupied part of the water column. However, a closer look at the vertical and temporal size distribution of specimens within each species revealed an overrepresentation of large specimens in depths at the beginning of the sampling (shortly after the full moon) and an overrepresentation of small individuals at the surface and subsurface by the end of the sampling (around new moon). These observations imply that a disproportionately large portion of the population followed for each species a canonical reproductive trajectory, which involved synchronised reproduction and ontogenetic vertical migration with the descent of progressively maturing individuals. This concept is consistent with the ini-

tial observations from the Red Sea, on which the reproductive dynamics of planktonic foraminifera has been modelled. Our data extend this model to non-spinose and microperforate symbiont-bearing species, but contrary to the extension of the initial observations on other species of foraminifera, we cannot provide evidence for ontogenetic vertical migration with ascent during maturation. We also show that more than half of the population does not follow the canonical trajectory, which helps to reconcile the existing contrasting observations. Our results imply that the flux of empty shells of planktonic foraminifera in the open ocean should be pulsed, with disproportionately large amounts of disproportionately large specimens being delivered in pulses caused by synchronised reproduction. The presence of a large population reproducing outside of the canonical trajectory implies that individual foraminifera in a fossil sample will record in the calcite of their shells a range of habitat trajectories, with the canonical trajectory emerging statistically from a substantial background range.

1 Introduction

The concept of synchronous reproduction followed by a predictable adjustment of depth habitat during ontogeny (ontogenetic vertical migration) has been the paradigm of population dynamics in planktonic foraminifera for more than half a century. Guided by instructive illustrations in publications and textbooks (Fig. 1 and reference therein), researchers have subsequently applied these concepts to interpret short-term variability in flux of empty shells (e.g. Lin, 2014; Jonkers et al., 2015; Venancio et al., 2016) and to estimate the po-

sition in the water column where the final chambers of the shells with their wealth of geochemical proxies have been produced (e.g. Steinhardt et al., 2015; Takagi et al., 2016). The paradigm is tightly linked with the notion that planktonic foraminifera are obligate sexual outbreeders (Hemleben et al., 1989). Indeed, this unusual reproductive strategy among unicellular plankton is congruent with, and perhaps even reliant on, the temporally and spatially coordinated release of gametes (Weinkauff et al., 2020).

Synchronised reproduction is known to occur among many marine organisms, such as corals, which are observed to spawn once a year synchronously within and even between communities, sometimes located hundreds of kilometres away (Babcock et al., 1986). Synchronous gamete release has also been observed in pelagic organisms such as marine algae (Brawley and Johnson, 1992). This type of synchronisation either requires an efficient internal biological clock or can be less efficiently but more economically triggered by external cues, such as the annual seasonal cycle or by periodic changes in nighttime illumination and tides, both linked to the lunar cycle (Clifton, 1997; Žuljević and Antolić, 2000).

Rhumbler (1911) was among the first to observe mass release of gametes in planktonic foraminifera, and this phenomenon has been since confirmed by laboratory observations in many species (Anderson and Bé, 1976, and reference therein; Bé et al., 1977; Hemleben et al., 1989, and references therein). That the mass release of gametes (hundreds of thousands, Spindler et al., 1978) may be synchronised was first noticed for the species *Hastigerina pelagica* (Spindler et al., 1979). Here, in situ observations (Almogi-Labin, 1984) and laboratory experiments (Spindler et al., 1979) showed a strong periodicity apparently aligned with the synodic lunar cycle but driven internally as it was observed in specimens kept in the laboratory, without exposure to any obvious lunar-cycle-related cues. Further research provided evidence for synchronised reproduction in other species of planktonic foraminifera, based on observations in the Red Sea (*Trilobatus sacculifer*, *Globigerinella siphonifera* and *Globigerinoides ruber*; Bijma et al., 1990; Erez et al., 1991; Bijma and Hemleben, 1994; Hemleben and Bijma, 1994) and in the North Atlantic (*Globigerina bulloides*, *Neogloboquadrina pachyderma* and *Turborotalita quinqueloba*; Schiebel et al., 1997; Volkmann, 2000; Stangeew, 2001). Observations of a periodicity (lunar, semilunar or even annual, Fig. 1) in foraminifera fluxes from sediment trap samples for the species *Orbulina universa*, *Globigerinella siphonifera* (*aequilateralis*) and *Globorotalia menardii* (Kawahata et al., 2002; Jonkers et al., 2015) further corroborated the notion that the reproduction of many species of planktonic foraminifera in the upper ocean is synchronised by periodic cues, related to the lunar cycle.

Next to the observation of synchronised reproduction, analyses of vertically resolved plankton tows from the Gulf of Eilat (also known as the Gulf of Aqaba) and central Red Sea led Erez et al. (1991) and Bijma and Hemleben (1994) to

introduce the concept of concerted vertical shift in the habitat of the synchronously reproducing population: the ontogenetic vertical migration (OVM). The notion that the reproductive cohort undergoes a concerted vertical movement (typically sinking) terminated by reproduction at a specific depth would further increase the chance of gamete fusion by co-locating their synchronous release in space. The mechanism facilitating such an orchestrated vertical migration is at hand: as the individual foraminifera grow, the weight of the calcite shell increases disproportionately, generating sufficient negative buoyancy to counteract passive movement by turbulence in the mixed layer, and the increasingly adult specimens embark on a collective descent to the reproduction depth (Erez et al., 1991). Like the concept of synchronised reproduction, OVM appeared to be supported by observations of distinct geochemical signatures associated with the final chambers of foraminifera shells, indicating that these were produced in different (typically deeper) parts of the water column than the rest of the shell (e.g. Pracht et al., 2019).

As a result, the (lunar, semilunar or annual) synchronous reproduction model associated with OVM has been generalised for most species of planktonic foraminifera (Fig. 1). These appealing and logical schemes became widely adopted, so much that we almost omitted that the presented depictions of life cycles of most species were idealised, that they still required additional observations, and that there remains a host of problems and uncertainties challenging the presented models. Next to the discovery of active photosymbiosis (Takagi et al., 2019) in species whose hypothetical OVM trajectories extend below the photic zone, there have been numerous observations of stable vertical habitats in the plankton (Rebotim et al., 2017; Iwasaki et al., 2017; Greco et al., 2019; Lessa et al., 2020) as well as shell flux patterns in sediment traps (Lončarić et al., 2005; Chernihovsky et al., 2020), showing no evidence of OVM and reproduction synchronised by the lunar cycle. Even where plankton tow and sediment trap could be interpreted as indicative for cohort growth (synchronised reproduction), the timing of reproduction with respect to the lunar cycle appeared to vary within species and among species (e.g. dephasing between *G. menardii* and *G. siphonifera* in Jonkers et al., 2015; reproductive event suspected after the full moon in Venancio et al., 2016; continuous growth of *T. sacculifer* up to 7 d after full moon in Jentzen et al., 2019), and the external cue responsible for the synchronisation remained unclear.

On a more conceptual level, the OVM phenomenon suffered from the lack of explanation for habitat depth restitution after gametogenesis. Whereas it can be easily shown that the adult, often “sinking”, part of the postulated OVM cycle is mechanically plausible, how the tiny (10–20 µm) gametes and zygotes succeed to ascend the same distance as the descending adults over a period of days and to emerge as small specimens intercepted by plankton nets at the surface remained unanswered. Similarly, the apparent necessity to synchronise gamete release in space and time to facilitate




Figure 1. Canonical view of the reproductive strategy of selected species of planktonic foraminifera with synchronised reproduction and ontogenetic vertical migration, modified after the idealised schemes proposed by Hemleben et al. (1989) and Schiebel and Hemleben (2005, 2017). “G.” indicates gametogenesis, with black dots depicting the gametes.

reproduction has been challenged by reports of the existence of an asexual mode of reproduction in at least two species of planktonic foraminifera from different clades (Takagi et al., 2020; Davis et al., 2020). Although the canonical concept of reproduction dynamics in planktonic foraminifera has been derived from observations, it remains unclear whether it applies to all species and whether it takes place at all times. This uncertainty is largely due to the lack of direct observational data obtained in the open-ocean habitat of planktonic foraminifera, which would reproduce the initial observations from the Red Sea and allow a direct assessment of reproduction dynamics for more species.

This is unfortunate considering the consequences of (lunar) synchronised reproduction and OVM have on the calibration of models simulating planktonic foraminifera population growth, for biogeochemical cycles and paleoproxies. With their calcite shell, planktonic foraminifera are major carbonate producers in the pelagic environment (e.g. Schiebel, 2002). Synchronised reproduction would generate pulses in the export flux of larger shells to the deep ocean and therefore impact marine biogeochemical cycles (Kawahata et al., 2002). Since foraminifera shells grow by sequential addition of chambers, the shell incorporates a sequence of chemical characteristics of all environments where the growth took place. Therefore, interpretations of the geochemistry of the shells require knowledge of where specimens grew. A widespread and extensive OVM in planktonic foraminifera populations, whether it concerns the entire population or just a small percentage of it, would generate inhomogeneity in the chemical composition of the concerned shells, which may

complicate the interpretation of the overall signal and especially of the signal recorded by individual shells.

The reproductive strategy of planktonic foraminifera can be best addressed by direct observations, capturing both the temporal and the vertical (ontogenetic migration) dimension. Such observations require vertically resolved sampling, replicated in time over the entire period of the proposed reproduction periodicity. Both requirements are hard to achieve, with oceanographic expeditions typically covering linear transects rather than remaining for weeks within the same water mass. Serendipitously, we were able to obtain a set of samples suitable to address at least to some degree the reproduction strategy of planktonic foraminifera in the north-east subtropical Atlantic ocean during the M140 cruise (Kučera et al., 2019). For a period of 2 weeks, the ship remained in a similar region, and we were able to obtain a set of vertically resolved plankton samples, which allows us to test the existence of a temporally synchronised reproduction and the presence of OVM in planktonic foraminifera in the open ocean. To this end, we measured and analysed the abundances and size distribution of four species – *Globigerinita glutinata*, *Globigerinoides ruber ruber*, *Globorotalia menardii* and *Orbulina universa*, representing all three main clades of extant planktonic foraminifera, with the fourth comprising only the Hastigerinidae.

2 Material and methods

2.1 Sampling

Because of the necessity to service two of the eastern sediment traps and moorings of the NIOZ trans-Atlantic array (Stuut et al., 2019), the R/V *Meteor* remained during the first 2 weeks of the cruise M140 (Kučera et al., 2019) within similar water masses in the eastern part of the tropical Atlantic ocean, north of 10° N (Fig. 2). This part of the Cape Verde Basin is characterised by the presence of the North Equatorial Current (NEC), the Guinea Dome (GD) in the south-east and the Intertropical Convergence Zone (ITCZ) in the south (Fig. 2). As highlighted by the sea-surface temperature (Fig. 2a), the region is also heavily affected by eddies where both cold and warm core eddies are characterised by upwelling and downwelling at their centres and margins. During the 2 weeks of the cruise, the population of planktonic foraminifera in the water column was sampled at nine stations (Fig. 2). Every day at 08:00 (local time) from the 12 to 14, the 17 to 21 and on the 25 August 2017, two successive sampling casts were carried out, using a multi-plankton sampler (MPS, Hydro-Bios, Kiel) equipped with five nets (100 µm mesh size, 0.25 m² opening) closing sequentially at successive discrete depths during the upcast. The first and deeper cast collected water at a speed of 0.5 m s⁻¹ from the intervals of 700–500, 500–300, 300–200, 200–100 and 100–00, while the second cast resolved the upper layer at intervals of 100–80, 80–60, 60–40, 40–20 and 20–0 (Table 1). The resulting 81 samples (nine vertical profiles resolved at nine depth levels) were processed either directly on board or stored by freezing and processed later. The samples were analysed without splitting. All specimens of planktonic foraminifera were picked and identified to the species level following the taxonomy of Schiebel and Hemleben (2017). Individuals bearing cytoplasm were assumed living and counted separately from what was considered empty shells. Following Morard et al. (2019) we use *Globigerinoides ruber ruber* instead of the commonly used *Globigerinoides ruber* pink.

The MPS was equipped with a pressure sensor, allowing net opening at precisely determined depths; a flow meter to determine directly the volume of water filtered by each net, later used to estimate planktonic foraminifera standing stocks; and a conductivity–temperature–depth (CTD) probe (SST CTDM90), recording CTD profiles at each station except for station 7, for which no profile was recorded. Despite the presence of eddies in the region, the CTD profiles showed overall similar physical conditions in the water, albeit with lower subsurface temperatures and salinities in the eastern part of the region and a shallower mixed layer depth (MLD), above 50 m depth (Fig. 2). The chlorophyll-*a* concentrations remained low (< 1.5 mg m⁻³), and the deep chlorophyll-*a* maximum (DCM) was located below the MLD (deeper DCM

Table 1. Station number (in brackets their reference name in Kučera et al., 2019), location (degree decimals), date of sampling and corresponding day in the lunar cycle (LD). The studied sampling depth intervals for all stations are 0–20, 20–40, 40–60, 60–80, 80–100, 100–200, 200–300, 300–500 and 500–700 m depth.

Station	Latitude	Longitude	Date	Lunar day
2 (GeoB22402)	15.871	–28.745	12 Aug 2017	20
3 (GeoB22403)	14.791	–32.507	13 Aug 2017	21
4 (GeoB22404)	13.721	–36.221	14 Aug 2017	23
6 (GeoB22406)	12.293	–36.942	17 Aug 2017	26
7 (GeoB22407)	12.096	–36.794	18 Aug 2017	27
8 (GeoB22408)	12.099	–30.378	19 Aug 2017	28
9 (GeoB22409)	11.880	–26.662	20 Aug 2017	29
10 (GeoB22410)	11.437	–22.818	21 Aug 2017	0
12 (GeoB22412)	14.112	–23.740	25 Aug 2017	4

found in station 4 and shallower in station 10 with respective depth of 83 and 45 m, Fig. 2).

2.2 Planktonic foraminifera size measurements

From among the identified and counted species, the three most consistently occurring among the stations were used to test for the existence of synchronised reproduction and OVM by measuring their shell sizes. All specimens (cytoplasm bearing and empty) of *Globigerinoides ruber ruber* ($n = 1073$), *Globorotalia menardii* ($n = 1085$) and *Globigerinita glutinata* ($n = 3520$) were manually transferred to customised microslides (Kreativika), oriented in the umbilical view and imaged using a Keyence digital microscope (VHX 6000) equipped with 100–1000 × magnification objective (VH-Z100R), an automated stage (VHX S650E) and an LED ring light (OP-88164). Size measurement calibration was performed automatically by the microscope by use of a calibration stage inset. Imaging was performed in confocal depth composition mode and magnifications ranging between 200 and 500 ×. The acquired images and elevation data were analysed with a custom script (MATLAB, 2017). The automated segmentation of foraminifera from the background occurred in two steps. A coarse primary segmentation was obtained by using only the elevation data to isolate particles from the background based on their height. The final particle segmentation was generated using an implementation of the sparse field method by Lankton (2009) on the RGB data with the previously generated segmentation mask as the seed area. Particle measurements were then performed on the final segmentation mask using the MATLAB Image Processing Toolbox (Fig. A1 in Appendix A). Among the available size parameters, we systematically used the minimum diameter for the analyses (further developed in Sect. 2.3) and referred to the length (in pixels) of the minor axis of the ellipse that has the same normalised second central moment as the region, returned scalar. The error range of the size mea-




Figure 2. (a) Map of the study area showing the position of the studied vertical profiles (black dots with numbers), remotely sensed sea-surface temperature (z axis; August 2017, aqua-MODIS 4 km resolution, data produced with the Giovanni online data system, developed and maintained by the NASA GES DISC), with the North Equatorial Current (NEC) and the Guinea Dome (GD) highlighted by black arrows (following Fieux, 2021, and references therein). (b) CTD salinity section with isopycnals (white, ranging from 1023 at the surface to 1027 below 300 m) and Chl- a concentration (mg m^{-3}) with isothermals (white, ranging from 27.5 at the surface to 7.5 °C below 600 m) and with stations highlighted by straight vertical white lines, triangles and numbers on top of the plot (no CTD profile was recorded for station 7). (c) Station profiles (coloured lines) of Chl- a concentration (mg m^{-3}) and temperature (°C). For all plots, the x axis is stretched in the top to allow a better observation of the mixed layer depth (MLD). Figures were drawn by Ocean Data View (Schlitzer, 2015).

surement is 1 μm per single measurement (i.e. per specimen). This allows us to identify specimens that are effectively of a similar size or larger than the size of the net mesh (100 μm). This is important because foraminifera smaller than the nominal mesh size often remain in the catch, because of clogging of the net or because the small specimens adhere to larger particles. Finally, the segmentation masks were manually checked for the presence of broken specimens and overlapping particles (foraminifera touching each other), which were all then removed from the dataset. In addition to the three species, we also analysed the occurrence of trochospiral ($n = 62$) and spherical ($n = 250$) stages of the species *Orbu-*

lina universa, which can be easily separated by the presence of the terminal chamber.

2.3 Data analysis

To compensate for the low abundances of specimens in the deeper net intervals and in order to treat the data in a coherent way with regard to the environmental parameters (e.g. depth of the MLD; see Sect. 2.1), we performed similarity analysis and grouped depth level intervals using absolute data and complete linkage. This led to a reduction of the original nine depth intervals into five new intervals: sur-

face 0–20 m, supra-epipelagic 20–40 m, epipelagic 40–80 m, infra-epipelagic 80–300 m and mesopelagic 300–700 m respectively located above, within and below the thermocline and DCM.

Because of the underlying (and expected) lognormal distribution of size and the fact that the sampling begins at 100 µm (size of the mesh), the size distributions are artificially truncated, and rather than trying to compensate for this by transformations, we decided to rely on non-parametric approaches in the analyses of such data. We therefore employed the Kruskal–Wallis test instead of ANOVA to assess the potential variability in abundance and size of the studied species across the five depth intervals and along the nine vertical profiles. Additionally, overall differences in the distribution of the data without any transformations were tested by a discrete Kolmogorov–Smirnov test. The statistical tests were formulated to evaluate specific hypotheses for *Globigerinita glutinata*, *Globigerinoides ruber ruber* and *Globorotalia menardii* only (specimens of *Orbulina universa* were not specifically measured but separated in the two categories “trochospiral” and “spherical” and did not occur in concentrations allowing statistical testing).

In the absence of synchronised reproduction, we would expect no significant differences within and between species in the shape of the overall size distribution among stations and random variability in planktonic foraminifera concentrations among the stations (for living and for dead specimens), reflecting patchiness (Siccha et al., 2012; Meilland et al., 2019).

In the absence of OVM within planktonic foraminifera species, we would expect for each species no significant differences in the shape of the size distribution across the depth intervals covering the habitat depth of the species.

In addition to the above-mentioned analyses, we also visualised the differences in the proportion of shells of a certain size occurring at a certain depth or time following the concept of Bijma et al. (1990). To this end, we transformed the analysed proportions across stations and sampling intervals into residuals of size classes, highlighting size classes that are over- (positive residuals) and underrepresented (negative residuals) at certain stations or sampling intervals:

$$\text{Residuals}_{\text{Station}} = (P_{\text{ST SC}_i}) - \left(\text{mean} \left(\sum_i^N P_{\text{ST SC}_i} \right) \right),$$

$$\text{Residuals}_{\text{Depth}} = (P_{\text{SP SC}_i}) - \left(\text{mean} \left(\sum_i^N P_{\text{SP SC}_i} \right) \right),$$

where P is the percentage of foraminifera, SC is the size class based on the specimens' minor axis, ST is the sampling station and SP is the sampling interval.

Following the method of Bijma and Hemleben (1994), the residuals were calculated on the sum of cytoplasm-bearing and empty shells, but because the proportion of the latter was low within the living zone, the results would be similar even if the analysis was limited to the cytoplasm-bearing shells.

In addition, we calculated relative mortality (%) per size class following the method described in Hemleben and Bijma (1994) as

$$\text{Relative mortality in SC}_1 = \frac{(\text{RA}_{\text{SC}_1} - \text{RA}_{\text{SC}_2})}{\text{RA}_{\text{SC}_1}} \cdot 100,$$

where RA is the mean relative abundance of foraminifera and SC is the size class based on the specimens' minor axis, with 1 being the smaller one and X being the larger one.

In a scenario of synchronised reproduction, this calculation uses the difference of foraminifera abundances between a smaller size fraction and a larger size fraction to estimate pre-adult mortality in the small size fractions and distinguish it from what could be attributed to post-reproduction mortality in the larger size fractions.

Residuals and relative mortality were calculated for foraminifera with minimum diameter larger than 100 µm to avoid potential bias due to differential net clogging. Relative mortality was not calculated for *Orbulina universa* as specimens were not measured but separated in only two categories: trochospiral and spherical.

3 Results

3.1 Planktonic foraminifera abundances, distribution and size

Over the sampling area maximum concentrations of the three species of planktonic foraminifera *Globigerinita glutinata*, *Globigerinoides ruber ruber* and *Globorotalia menardii* were observed between 0 and 40 m and at the end of the cruise. *Orbulina universa* were most abundant above 60 m, with the highest abundance at the beginning of the cruise. *G. glutinata*, *G. ruber ruber* and *G. menardii* have a clear surface maximum reaching up to 79, 47 and 122 individuals m⁻³ respectively between 0 and 20 m at station 12. The highest concentration of *O. universa* (12 individuals m⁻³) was observed at station 2, between 40 and 60 m (Fig. 3a). As shown in Fig. 3b, the occurrence of foraminifera was spread over several sampling depth intervals for the first stations and narrowed down to the two shallowest depth intervals by the end of the cruise, at stations 10 and 12. This is particularly visible for *G. menardii* and *O. universa*. The ratio between living and dead specimens (Fig. 3c) shows a decreasing proportion of living specimens with depth over the sampled time interval. For *G. glutinata*, the proportion of dead specimens is particularly high below 60 m. For all other species this occurs deeper in the water column, below 100 m (Fig. 3c).

Overall, specimens of *G. glutinata*, *G. ruber ruber* and *G. menardii* were rather small, with a respective median size of 119, 122 and 135 µm when only considering specimens larger than 100 µm to avoid a potential net clogging bias (Fig. 3d; Tables A1, A2 and A3 in Appendix A). Specimens




Figure 3. *Globigerinita glutinata*, *Globigerinoides ruber ruber*, *Globorotalia menardii* and *Orbulina universa* (a) abundances (individuals m^{-3}), (b) normalised abundances per day (%), (c) ratio between living and dead specimens, and (d) average size based on the minor axis (μm) and excluding all specimens smaller than $100 \mu\text{m}$, per depth interval (y axis) and per station and date (x axis). White squares represent the absence of specimens. For *O. universa* panel (d) displays the percentage of trochospiral specimens, with yellow indicating trochospiral specimens only and dark blue indicating spherical specimens only.

of *G. glutinata* appear to be slightly larger than above 60 m at every station, especially for station 3 where the maximum average size is observed between 60 and 80 m ($149.4 \mu\text{m}$). The largest specimens of *G. ruber ruber* were observed at station 2, between 100 and 200 m and between 500 and 700 m and with a respective average size of 253 and $259 \mu\text{m}$, but otherwise no clear tendency emerged. Larger individuals of *G. menardii* were recorded at station 2, from 20 to 200 m and with an average size larger than $500 \mu\text{m}$ ($534 \mu\text{m}$ in 20–40 m, $539 \mu\text{m}$ in 40–60, $508 \mu\text{m}$ in 60–80 and $501 \mu\text{m}$ in

100–200 m depth), strongly contrasting with the small size of specimens collected at every other station and particularly larger than the individuals collected at the end of the cruise (below $140 \mu\text{m}$ at station 12). For *O. universa*, a larger proportion of trochospiral specimens was observed between 0 and 40 m in stations 6, 8 and 9. In stations 4 and 12 they were dominant between 80 and 100 m (Fig. 3d).

3.2 Statistical analyses for synchronised reproduction

The statistical analyses for the abundance and size data of *Globigerinita glutinata*, *Globigerinoides ruber ruber* and especially of *Globorotalia menardii* (living and dead) do not provide evidence against the existence of synchronised reproduction among the studied populations of these species.

Based on a discrete Kolmogorov–Smirnov test, the size distributions in stations 10 and 12 statistically differ from the distributions observed at (almost) all other stations. Specifically, living specimens of *G. glutinata* were significantly larger at the beginning of the sampling period than at the end. For example, individuals at station 2 were larger than at stations 6, 7, 8, 9 and 12, and individuals at station 3 and 4 were larger than at stations 6, 8 and 9. Specimens collected in station 8 were smaller than in stations 10 and 12 (Fig. 4a, Table A4).

Significantly higher abundances of living specimens of *G. menardii* were observed in station 10 between 0 and 60 m. The specimens (dead and living) of *G. menardii* collected in stations 2, 3 and 4 were larger than those collected by the end of the cruise, for example in stations 8, 9, 10 and 12 (Tables A4 and A5). Living individuals of *G. menardii* in station 12 were significantly smaller than those collected from station 2 to 4 but larger than those collected between station 8 and 10 (Fig. 4a, Table A4). In station 10, living specimens of *G. menardii* were significantly smaller than those collected at the beginning of the cruise from station 2 to 4 and in the last sampled station (station 12). We can therefore conclude that a significant influx of small living specimens of *G. menardii* occurred in station 10.

Over the sampling area living individuals of *G. ruber ruber* were significantly more abundant in station 3, 9 and 10 (0 to 20 m), in station 8 (20 to 40 m), and in station 12 (0 to 40 m) than in the other stations and depth intervals. Living specimens of *G. ruber ruber* were significantly larger in station 2 and 3 than in any other stations collected by the end of the cruise (stations 7 to 12) where no significant differences in size could be observed (Table A4). The larger dead specimens of *G. ruber ruber* were also observed in station 2. These results indicate the presence of larger specimens of this species (living and dead) at the beginning of the sampling and higher abundances in surface waters from station 9 onwards.

3.3 Statistical analyses for ontogenetic vertical migration

For *G. glutinata* the mean size of living specimens between 0 and 20 m depth was significantly larger than between 40 and 80 m and significantly smaller than between 80 and 300 m (Fig. 4b, Table A5). The mean size between 40 and 80 m was significantly smaller than in all other depth groups, and the mean size between 80 and 300 m was larger than in all shallower depth intervals. The size data for *G. glutinata* therefore

do not show any clear signal of OVM. In contrast, we observe a successively increasing size of the living specimens with depth in *G. ruber ruber*. The size of the living individuals of *G. ruber ruber* was significantly larger below 40 m (Fig. 4b, Table A5), supporting the existence of OVM. Similarly, we also observed a successively increasing size with depth for *G. menardii*. Specifically, specimens collected between 0 and 20 m were smaller than those below 40 m. Specimens between 40 and 80 m were significantly larger than those collected between 0 and 20 m, and specimens between 80 and 700 m depth were significantly larger than those collected between 0 and 40 m depth (Fig. 4b, Tables A2 and A5).

3.4 Disproportional occurrence of foraminifera within specific size fractions over time (synchronised reproduction) and depth (OVM)

Visualisation of the residuals of foraminifera occurrence among the different shell size fractions with time and depth allows for a quick identification of size classes that are over- and underrepresented at certain stations or depth intervals in comparison to the whole dataset (Fig. 5). As explained in the material and method section (Sect. 2.3.), residuals were calculated for specimens larger than 100 μm only and therefore excluded about 22 % of the collected individuals of *G. glutinata*, 28 % of *G. ruber ruber* and 31 % of *G. menardii* (Table A1). For *Orbulina universa* we treated trochospiral and spherical specimens as two size fractions and calculated the residuals accordingly.

Small specimens of *G. glutinata* appear disproportionately more abundant at the beginning of the cruise at station 2 and then again at stations 7 and 8 (Fig. 5a). Across the different depth intervals (Fig. 5b) we can notice an overrepresentation of small individuals (100–120 μm) and underrepresentation of larger individuals above 40 m. Below 40 m, the opposite pattern emerges, with a systematic underrepresentation of specimens in the smaller size fraction and an overrepresentation in the larger ones (120–200 μm).

Over time, large specimens of *G. ruber ruber* (> 220 μm) appear overrepresented at the beginning of the cruise (stations 2 and 4) and underrepresented after 6 d (from station 6 and 7). Conversely, very small specimens (< 140 μm) are overrepresented from the sixth day of sampling, from station 6 (only exception for station 10, Fig. 5a). Vertically, individuals of *G. ruber ruber* larger than 180 μm are overrepresented within the production zone (Figs. 3c and 5b).

Residuals for the specimens of *G. menardii* show a clear signal over time and water depth intervals. Large specimens (> 200 μm) are overrepresented during the first 6 d of sampling (station 2 to 6) with very large specimens (> 500 μm) being overrepresented during the first 2 d (station 2 and 3, Fig. 5a). From the seventh day of sampling the trend is inverted with a clear overrepresentation of small specimens (< 200 μm) until the last day of the sampling. Vertically,




Figure 4. Size distribution of living specimens for the three studied species (a) across the different stations and (b) across the depth profile from the surface (0–20 m depth) to the mesopelagic environment (300–700 m depth). Green dots indicate outliers. The boxes extend to the interquartile range (IQR), and the whiskers indicate $1.5 \cdot \text{IQR}$. The green lines in the boxes indicate the median.




Figure 5. Proportions of specimens of the three studied species of planktonic foraminifera expressed as residuals, highlighting size classes that are overrepresented (red tones) or underrepresented (blue tones) for specific (a) days (y axis) in comparison to the whole dataset, with FM and NM highlighting the time of the full moon (21 August) and of the new moon (before the sampling started, on the 7 August); and (b) depth intervals (y axis) in comparison to the whole dataset. The grey filter indicates the depths where > 50 % of the specimens were dead (empty shells), and the intercepted filled shells therefore likely represent background mortality across the different size fractions (Peeters and Brummer, 2002).

these small specimens are only overrepresented between 0 and 40 m, below which larger specimens ($> 200 \mu\text{m}$) are systematically taking over.

Because the concentrations of *O. universa* along the study were lower than for the other species (Fig. 3a), its residuals should be treated with care. However, trochospiral specimens of *O. universa* were overrepresented in surface waters at stations 8 to 12 and from 0 to 20 m, while spherical ones are overrepresented during the first half of the cruise and below 40 m depth.

Observation of the residuals of *G. glutinata*, *G. ruber ruber*, *G. menardii* and *O. universa* over the depth intervals (Fig. 5b) therefore support the existence of an OVM, with larger specimens overrepresented below 20 m (*G. ruber ruber*) and 40 m (*G. glutinata*, *G. menardii* and *O. universa*) and smaller (living) specimens overrepresented at the surface. A pattern of synchronicity in the reproduction cannot be excluded and residuals of *G. ruber ruber* and especially of *G. menardii* and *O. universa* support such a model with an overrepresentation of large specimens (potential mature adults) shortly after the full moon and at the beginning of the cruise, as well as of small specimens (potential juveniles) around the new moon and by the end of it.

3.5 Mortality/population loss and expected size of maturity

Assuming our sampling intercepted a largely similar regional population, affected in abundance only by patchiness, with reproduction synchronised similarly for the different species, the obtained size data could be used to estimate the size class where reproduction begins (Fig. 6; Hemleben and Bijma, 1994; Schiebel et al., 1997). To determine the size class in which one could expect maturity and higher chances of reproduction, we determined the loss rate of each size class in the first 100 m (production zone) across all stations and generated histograms of relative mortality for each species (Fig. 6). For the three species over the studied area, especially for *G. menardii*, the population was largely dominated by the presence of foraminifera in the smaller size class (Fig. 6a), with abundance decreasing with size. Because the zygotes (youngest individuals) are overproduced per individual even with the limited rate of reproductive success (a mean of 21 zygotes per individual in the entire population, Weinkauff et al., 2020), the mortality in planktonic foraminifera is expected to be very high among the smallest size class. It should then decrease until a point when maturity is reached and mortality increases until 100 % in the largest size class. This is because the life of a foraminifera ends with gamete release (Bé et al., 1977).

In all three analysed species, the apparent mortality profiles show patterns that can be explained in terms of the hypothetical models. For *G. glutinata*, mortality increases with size (Fig. 6a), indicating that across all size classes we observe post-reproduction mortality (i.e. mostly specimens who

reproduced) and the minimum size of maturity is below the studied size range.

Mortality for *G. ruber ruber* is highest among specimens with a size between 100–140 μm ($> 77\%$) and then again among the specimens larger than 340 μm . Based on the hypothetical model, the high relative mortality in the smaller size fractions could be attributed to pre-adult mortality, while the increase towards the larger size fraction likely signals post-reproduction mortality. The derived size from which reproduction of *G. ruber ruber* can safely be expected in our data would occur around 300 μm . Without clear proof of reproduction such as the presence of gametogenetic calcite on top of the shell (Schiebel et al., 1997), it is, however, difficult to provide a precise size fraction from which reproduction occurred, and one should not exclude that reproduction has started from the size class 140 to 180 μm .

Higher relative mortalities for *G. menardii* are observed for specimens belonging to 100–200 μm and larger than 600 μm . Similarly to what is observed with *G. ruber ruber*, the relative mortality in the smaller size fractions could be attributed to pre-adult mortality, while the ones in the larger size fractions likely highlight post-reproduction mortality. The inferred optimal size of reproduction for *G. menardii* would be around 500 μm , but as previously mentioned without proof of reproduction and based on the relative mortality profile (Fig. 6b), one should not exclude that reproduction has started already from the size class 300 to 400 μm .

4 Discussion

4.1 Evidence for regionally synchronised reproduction

The studied material comes from nine stations covering a geographical area extending from 22.818 to 36.942° W and from 11.437 to 15.871° N (Fig. 2a). This sampling area is heavily affected by eddies (Fig. 2a) generating a vertical transport of water bodies and consequently of planktonic foraminifera both up and down in the water column that could affect their population dynamics. In addition, we observed a slight variability in the environmental parameters acquired by the CTD, such as temperature and salinity (Fig. 2c). It is therefore important to stress that our observations probably reflect the dynamics of multiple populations of foraminifera rather than of a single one. Small individuals were present throughout the entire survey in significant proportions for all species (Figs. 3d and 6a). Similarly, dead specimens of all species and all sizes were observed at every station (Fig. 3c) and never with a significantly higher or lower ratio. The constant presence of small and dead specimens of foraminifera from all species suggests that reproduction may have occurred continuously during our survey.

However, at the beginning of the cruise (stations 2 to 6) all four species occurred at low standing stocks, and their assemblages systematically comprised the largest specimens




Figure 6. Top- and bottom-left plots show an idealised picture (model) of planktonic foraminifera mean abundance and relative mortality per size fraction in the first 100 m depth with the size from which one can expect reproduction located at the junction of the pre-adult mortality and mortality post reproduction (based on Bijma and Hemleben, 1994; Schiebel et al., 1997). The three top- and bottom-right plots show per species and size fraction (a) mean abundance (individuals m^{-3}) of planktonic foraminifera (all stations together) and (b) relative mortality (%) over the sampling time (see methods for the relative mortality calculation).

encountered throughout the entire cruise (Fig. 3b and d and Fig. 5a). Conversely, populations sampled by the end of the cruise (stations 9 to 12) were characterised by higher concentrations of foraminifera (factor 10) and comprised smaller specimens (overrepresentation of the small size fractions, Fig. 5a). This is particularly visible in the residuals of *Globorotalia menardii* (Fig. 6a) showing a statistically significant overrepresentation of large specimens (500–600 and 600–700 μm) in the two first sampled stations, visited 4 d after the full moon, and a statistically significant overrepresentation of small specimens (100–200 μm) from station 7 (3 d before the new moon). Similarly, the residuals of *G. ruber ruber* also indicate an overrepresentation of larger specimens on the first day of sampling and a dominance of small specimens from station 6 (Fig. 5a). Indeed, the development of the residuals for *G. ruber ruber* resembles the pattern that was observed about 30 years ago in the Red Sea and used to support the concept of synchronised reproduction (Bijma et al., 1990). Although not as clear, a signal of synchronicity in the reproduction can also be extracted from the size data of *G. glutinata*, with the larger recorded specimens emerging the second day of sampling (Fig. 3d) and an overrepresentation of the smaller size fraction in station 7 and 8 (Fig. 6a). Finally, higher concentrations and an overrepresentation of spherical specimens of *O. universa* (spherical chamber equals relatively close gametogenesis, Caron et al., 1987; Spero et al., 2015) were observed during the first days of sampling, and from station 8, trochospiral forms (likely younger) were dominant (Fig. 5). All of these observations

hint at the existence of synchronous reproduction in phase with the lunar cycle (Bijma et al., 1990).

Thus, despite persistent occurrence of cytoplasm-bearing small specimens throughout the monitoring period, the observed abundance and size patterns in the studied species are consistent with a significant portion of their populations being involved in a synchronised reproduction. Although the sampling interval in this study is too short to robustly estimate the involved generation time and assess any potential periodicity, we note that in all species disproportionately large amounts of large specimens were observed shortly after the full moon and disproportionately large amounts of small ones were detected about 10 d later (Fig. 5a). This observation is consistent with synchronisation by full moon, suggested by Bijma et al. (1990) and observed in some sediment trap time series (Jonkers et al., 2015). Since our sampling comprised populations covering a geographically large area, and we still observed hints for synchronised reproduction, it is likely that the synchronisation acted across a large part of the ocean, which would require triggering by an external cue or internal biological clock. In such a scenario, the synchronisation or reproduction in planktonic foraminifera would involve all populations at the same time and be recorded consistently across large geographical areas. This is supported by the observation that the calculated mortality profiles can be reconciled with the hypothetical model, which requires synchronous reproduction across the studied region. Such a large-scale synchronisation is also consistent with observations of synchronised reproduction in *G. bulloides* based

on material collected over different years, seasons and geographical areas (Schiebel et al., 1997).

4.2 Evidence for ontogenetic vertical migration (OVM)

The concept of ontogenetic vertical migration suggests that adult specimens of planktonic foraminifera proliferate at a specific depth where they encounter optimum conditions, such as the pycnocline or the nutrient-rich deep chlorophyll-*a* maximum (DCM) (Murray, 1991), to release their gametes. In the OVM schemes presented in the literature (Fig. 1), the adults either progressively sink during growth and the gametes released at depth ascend to reconstitute the depth range of juvenile specimens (e.g. *G. ruber* and *O. universa*) or the large specimens ascend and the gametes released at the shallow reproduction depth descend (e.g. *G. menardii* and *G. truncatulinoides*).

In our data, specimens from the smallest size fraction dominated the populations at all times and all depths, which would intuitively speak against the existence of any kind of OVM (Fig. 3d). However, the observed size distributions in all species can be reconciled with the existence of OVM, if we consider at what times and depths certain size classes are overrepresented or underrepresented with regard to their overall mean abundance (Fig. 5). Yet, our observations for *G. glutinata*, *G. ruber ruber*, *G. menardii* and *O. universa* only support OVM with sinking of maturing specimens followed by gamete ascent. This contrasts with the OVM pattern suggested for *G. menardii* by Schiebel and Hemleben (2017), according to which pre-adult specimens of this species inhabit a subsurface environment, ascending towards the end of their life for reproduction to the pycnocline/DCM, and the released gametes descend to reconstitute the deeper habitat of the pre-adult population. Our data provide no support for the ascending OVM pattern, and our observations of the population remaining in the upper water layer, with descent of adults to a depth of 80 m, are consistent with the fact that *G. menardii* harbours symbiotic algae, which are photosynthetically active in specimens of all sizes (Takagi et al., 2019). This could suggest that the OVM pattern varies regionally and based on the ecological conditions. Our samples included species representing all the major clades, so the pattern of OVM clearly does not appear to be limited to the spinose planktonic foraminifera, from where all of the existing evidence to date originated. On the other hand, all of the analysed species are symbiont bearing, which means the observed reproductive strategy, or some aspect of it, such as the nature of the synchronisation by cues related to light, which would be sensed by the symbionts, or the direction, with descending adults and ascending gametes, could be specific to symbiont-bearing taxa. Asymbiotic and deep-dwelling taxa may follow other reproductive strategies or differently configured ontogenetic trajectories. Similarly to the scheme of Schiebel and Hemleben (2017), and consistently with the numerous observations of species-specific typical living depths, our data

indicate that for each species the OVM reaches a different depth. Remarkably, in all cases, although the OVM reaches below the mixed layer, the habitat of the studied species remains systematically well above the DCM (Fig. 2).

Irrespective of its direction and the depth where it occurs, the existence of ontogenetic vertical migration could be advantageous for planktonic foraminifera. It may bring mature specimens away from predators (Erez et al., 1991), increase chances for gamete encounters (Weinkauff et al., 2020), and separate the habitats of maturing specimens and juveniles, which differ in size by an order of magnitude and likely follow different trophic strategies (Brummer et al., 1986). Also, the migration could even be the trigger for synchronous reproduction because descent through the water column induces a change in light intensity, and a certain threshold light level could act as a cue inducing reproduction. To engage in an OVM trajectory with descent of maturing specimens, our hypothesis, as suggested by Erez et al. (1991), is that rather than actively migrating, the foraminifera passively sink as their shells grow, and the addition of new chambers and shell thickening progressively increases the effective density of the individual (e.g. Bé and Hemleben, 1970; Bé et al., 1980; Erez, 2003). This theory corroborates recent observations of increasing shell density with size and with depth for specimens of *Globigerina bulloides* in the North Pacific Ocean (Iwasaki et al., 2019) and for living specimens of *Neogloboquadrina pachyderma* in the Barents Sea (Ofstad et al., 2021). The observed species-specific depth habitats (e.g. Bé, 1962; Fairbanks et al., 1982; Rebotim et al., 2017) would in this model emerge from differences in buoyancy due to different shell architecture and calcification, allowing the maturing specimens of different species to reach different target depth, where they remain until reproduction, with the resulting pattern being consistent with the often observed species-typical habitat depths. In this model, most of the motion would happen within small size fractions of the population, escaping observation when the populations are sampled by coarse mesh sizes ($> 100 \mu\text{m}$).

Next to the regulation of buoyancy by shell architecture and calcification, the descent of maturing individuals could be further achieved by (1) changes in the composition of the cytoplasm (such as changes in low-density lipid concentration; Spindler et al., 1978); (2) changes in Reynolds number due to adjustment of the effective specimen size by rearranging the rhizopodial network (Takahashi and Bé, 1984); (3) the properties of fibrillar bodies hypothesised to help foraminifera maintain their vertical position (Anderson and Bé, 1976; Hemleben et al., 1989); or (4) through changes in the production of low-density osmolytes, as observed in marine phytoplankton (Boyd and Gradmann, 2002). Whereas there may exist multiple mechanisms to explain how larger planktonic foraminifera can be found deeper and sustain themselves at specific depth intervals until reproduction, it is less obvious how gametes and/or juveniles can then rapidly ascend to reconstitute the shallowest habitat of the OVM tra-

jectory. Our observations indicate that the depth restitution would occur within 5 to 8 d of gamete release and involves vertical movement of 20–80 m. A large part of the movement would occur within the mixed layer (~40 m, Fig. 1), where turbulence could facilitate dispersion of the very young and light juveniles, transporting sufficient numbers of them towards a shallow optimum depth, increasing their chances to survive and embark on the canonical OVM trajectory. However, for *G. glutinata* and especially *G. menardii*, the ascent begins below the mixed layer, requiring 20–40 m of active movement. This can be achieved by positive buoyancy of the juveniles, facilitated by sparse calcification and/or low-density osmolytes (Boyd and Gradmann, 2002). Another possibility could be the ascent of the motile flagellated gametes with a dominant positive vertical component (phototaxis). Sexual reproduction in planktonic foraminifera involves the release of thousands of flagellated, motile gametes that also contain energy reserves (Anderson and Bé, 1976; Bé et al., 1977; Hemleben et al., 1989).

4.3 The canonical reproductive behaviour emerging among other reproductive dynamics

Although our data provide evidence for the existence of OVM and cannot exclude synchronous reproduction, in all taxa the signal of the typical canonical reproductive trajectory exists alongside a substantial noise, with dead and small specimens occurring at all times throughout the water column (Figs. 3c and 6b). To estimate the percentage of the population that does not follow the canonical path of synchronised reproduction and OVM, we calculated the proportion of individuals found in all squares of the diagram in Fig. 7 which do not follow the canonical trajectory (Fig. 7). The results suggest that about 75 % of *O. universa* may follow the canonical trajectory of synchronised reproduction and the OVM, but based on much larger sample sizes and therefore offering more reliable estimates, more than 50 % of *G. menardii* and up to 70 % of *G. glutinata* and *G. ruber ruber* do not appear to take part in synchronised reproduction, and about 50 % of *G. glutinata* and more than 60 % of *G. menardii* and *G. ruber ruber* do not appear to migrate vertically during ontogeny in the same way as the canonical trajectory.

Clearly, it is possible that the canonical reproductive behaviour emerges as a result of a stochastic pattern facilitated by the enormous overproduction of gametes. It has been previously estimated that only 5 % of the offspring may reach a mature reproductive stage (Brummer and Kroon, 1988), likely because the majority of this 5 % followed the optimal ontogenetic trajectory, whereas the rest are by chance stranded outside of the optimal trajectory and are less likely to reach maturity. This is supported in our data by high estimated mortality (> 75 %) in the smaller size fraction of *Globigerinoides ruber ruber* (< 140 µm) and *Globorotalia menardii* (< 200 µm, Fig. 6b) that we attribute to selection

among juvenile individuals dispersed along numerous ontogenetic trajectories, more or less suitable for survival and growth. As a result, only a small fraction of the pre-adult small specimens appears to reach the size range where reproduction, leading to mortality, is observed (Fig. 6a). This very large mortality was not observed in the smaller size fraction of *Globigerinita glutinata* probably because the juvenile specimens of this small species were smaller than 100 µm and remained below the detection limit of our sampling. Planktonic foraminifera whose trajectory follows the optimum ontogenetic trajectory for each species given its physiology (e.g. light for symbionts) are more likely to persist, and a release of gametes at the optimum target depth where most of the successful specimens gather will more likely lead to the production of juveniles. Thus, the synchronisation causes positive feedback, ensuring enough individuals will follow the optimum trajectory, but this is achieved on the cost of many individuals departing from it and making the canonical pattern hardly perceivable in observational data.

This partly explains why, as mentioned in the introduction, the model of synchronised reproduction has been challenged by the absence of recordable signal in many sediment trap and plankton tow studies (Lončarić et al., 2005; Rebotim et al., 2017; Iwasaki et al., 2017; Greco et al., 2019; Lessa et al., 2020; Chernihovsky et al., 2020). However, the concept of the emergence of the canonical trajectory from a large background juvenile mortality was raised already in one of the first studies dedicated to the synchronisation concept in planktonic foraminifera (Bijma et al., 1990). This aspect of the reproductive strategy model progressively faded behind instructive diagrams (Fig. 1) sometimes interpreted literally, inferring that a majority of specimens follow the ontogenetic trajectory described.

Finally, it remains unclear what role asexual reproduction plays in the overall population dynamics of the studied species. Recent observations for *Neogloboquadrina pachyderma* (Davis et al., 2020) and *Globigerinita uvula* (Takagi et al., 2020) show that planktonic foraminifera can reproduce asexually. If the proportion of specimens reproducing asexually is large, this process, which does not require synchronisation, could also explain the occurrence of small and large specimens at all times.

4.3.1 Implications for proxies and biogeochemical cycles

The signals of synchronised reproduction and OVM in our data are embedded within a large overall variability of the distribution of planktonic foraminifera individuals. Except for *O. universa*, we estimate that more than half of planktonic foraminifera individuals in the studied size range do not follow the canonical OVM and synchronisation trajectory. As a large portion of these specimens will reach the sediments, these differences in individuals life histories of planktonic foraminifera can partly explain various observations in proxy




Figure 7. A model describing the canonical ontogenetic trajectory of *G. glutinata*, *G. ruber ruber*, *G. menardii* and *O. universa* as recorded in the studied material. The residuals (further discussed in 2.3 and 3.4) highlight size classes that are overrepresented (red tones, “+”) or underrepresented (blue tones, “-”) across time (a), with FM meaning full moon and NM meaning new moon, and depth (b) in comparison to the whole dataset. Every coloured square indicates the presence of specimens and shows that foraminifera of all sizes were collected at almost all depths and times throughout the survey. Based on our observations the horizontal black lines in (b) represent the depth from which > 50 % of specimens are dead, and the vertical black arrows illustrate the flux of empty shells. Based on our interpretations (see results and discussion) “G.” in both panels hypothesises gametogenesis and the presence of gametes followed by gamete dispersions (associated grey arrows). The curved grey arrows highlight the hypothetical ontogenetic trajectories of specimens (gametes to reproductive stage) across time and depth.

variability measured on a single-specimen level. It has for example been shown that small specimens of foraminifera generally have a lower $\delta^{18}\text{O}$ and $\delta^{13}\text{C}$ value than larger specimens of the same species, among other factors also likely due to the OVM throughout their life (Berger et al., 1978; Hemleben et al., 1985). Therefore, the existence of different ontogenetic trajectories leading to the flux of empty shells within the same population should translate into a large variability in the geochemical composition of individual shells superimposed on an overall average signal, consistent with the canonical ontogenetic trajectory. This is partly overcome by the use of large specimen shells that belong to a narrow size fraction for geochemical analyses.

For single-specimen analyses, Haarmann et al. (2011) reported a large range of Mg/Ca derived calcification temperatures for *Globigerinoides ruber ruber* obtained from the same sample, which can be explained if the specimens followed different OVM trajectories. Similar observations were made in combined analyses of Mg/Ca and $\delta^{18}\text{O}$ in fossil specimens of (among others) *G. ruber ruber*, reporting unexpectedly large variability among the individual foraminifera

(Groeneveld et al., 2019). Our results indicate that such variability may result from variability in ontogenetic trajectories among individuals within the same population, as already hypothesised and discussed in the 1980s by Schiffelbein and Hills (1984), concluding that depth habitat and production seasonality could partly explain variability in their data.

The same phenomenon would also affect variability in the geochemical composition of successive chambers in the same individual. The canonical trend reflecting the optimum OVM trajectory would emerge on the background of variability in OVM trajectories recorded among the individual specimens. In both cases, the reproductive strategy model revealed by our study implies and reaffirms that geochemical analyses made on a large pool of specimens should reveal a signal of average calcification depth and time consistent with the canonical ontogenetic trajectory, whereas analyses of single individuals should reveal a large variability, even when the collected specimens originated from the same population.

In addition to the consequences for the interpretation of paleoceanographic proxies, the existence of synchronised re-

production should induce short-term dynamics in pelagic carbonate flux, for which planktonic foraminifera are one of the major contributors (Schiebel, 2002). Indeed, in the equatorial ocean, synchronicity (lunar or other) in the reproduction of *G. ruber* and *O. universa* has been invoked as an explanation for a periodicity in the flux of empty shells intercepted in sediment traps (Kawahata et al., 2002; Venancio et al., 2016). This suggests that the already well documented seasonal variability in species flux (e.g. Mohiuddin et al., 2004; Lončarić et al., 2005; Salmon et al., 2015) is likely composed of regular short pulses of disproportionately large amounts of disproportionately large specimens. The consequences of such a pulsed pattern of pelagic carbonate export flux for biogeochemical cycling such as the biological carbonate pump remain an important target for future studies.

5 Conclusions

Using new direct observations, the first from a tropical open-ocean setting, we were able to test for the existence of a synchronised reproduction and ontogenetic vertical migration in four symbiont-bearing species of planktonic foraminifera representing all three main clades.

Our observations of abundances, presence/absence of cytoplasm and size measurement for the species *Globigerinita glutinata*, *Globigerinoides ruber ruber*, *Globorotalia menardii* and *Orbulina universa* revealed a constant dominance of small specimens and the presence of living and dead specimens within all size fractions at all depths and time. However, superimposed on this pattern was a subtle but statistically significant signal indicating disproportionality in the abundance of individuals within specific size fractions with depth and through time in a way that is consistent with both synchronised reproduction and ontogenetic vertical migration via descent of maturing individuals (Fig. 7).

Our data show an overrepresentation of large specimens of *G. ruber ruber* below 20 m and of *G. glutinata*, *G. menardii* and *O. universa* below 40 m depth at the beginning of the cruise (shortly after full moon) and an overrepresentation of small specimens in the surface layer above these depths (Fig. 7) 5 to 8 d later. These observations imply that planktonic foraminifera population dynamics in the open ocean (at least for the studied species) involves synchronised reproduction and vertical migration of adult specimens. Since our sampling covered a substantial area, this pattern must affect planktonic populations regionally in the same way.

In all four species, we observe descent of mature specimens during ontogeny (OVM), which we attribute to a combination of passive processes that allow each planktonic foraminifera species to reach and sustain a specific depth of optimal ecological conditions (preferential depth, in our study not tied to the MLD or to the DCM) where they undergo gametogenesis. We speculate that descent (rather than ascent) of mature specimens is the common direction of OVM in the open ocean, at least for species bearing symbionts, and that motility of gametes may aid in depth restitution of juvenile specimens.

As we show that a large fraction of the population does not follow the canonical trajectory, sedimentary assemblages probably contain a mixture of specimens recording a range of individual trajectories in time and space, among which the canonical trajectory emerges only as a slight but significant disproportionality in abundances. This is because next to the canonical trajectory other reproduction-triggering parameters and reproduction types (e.g. asexual reproduction) may occur.

The model extracted from our dataset with the canonical signal of synchronised reproduction and OVM occurring on the backdrop of other ontogenetic trajectories (Fig. 7) helps reconcile previous contrasting observations. It implies that, in the sedimentary record, fossil shells of foraminifera carry a signal of different vertical life trajectories and that the background signal of synchronised reproduction that emerged may also generate a pulse in the periodicity of the flux of mature specimens to the deep ocean and thus impact the short-term carbonate export.

Appendix A

Table A1. Size variability (minor axis, in μm) of the measured specimens of planktonic foraminifera per species over the study when all and only specimens larger than 100 μm are considered, with N being the exact number.

		<i>Globigerinita glutinata</i>		<i>Globigerinoides ruber ruber</i>		<i>Globorotalia menardii</i>	
		All	> 100 μm	All	> 100 μm	All	> 100 μm
N		3520	2734	1073	762	1085	746
Minor axis (μm)	Minimum	37	100	21	100	59	100
	Median	113.99	118.7	114.38	122.3	116.19	134.9
	Mean	114.36	122.6	119.21	134.6	160.71	195.4
	Maximum	216	216	389	389	791	791

Table A2. Number of living specimens (N) and mean size (minor axis, in μm) of planktonic foraminifera per species and depth intervals.

Environment	Depth interval (m)	<i>Globigerinita glutinata</i>		<i>Globigerinoides ruber ruber</i>		<i>Globorotalia menardii</i>	
		N	mean	N	mean	N	mean
Surface	0–20	995	107.4	357	98.3	805	135.1
Supra-epipelagic	20–40	525	107.8	109	111.3	78	180.1
Epipelagic	40–80	209	102.2	51	125.7	51	293.6
Infra-epipelagic	80–300	203	114.9	132	133.4	64	305.6
Mesopelagic	300–700	49	114.5	18	135.0	29	186.4

Table A3. Number of living specimens (N) and mean size (minor axis, in μm) of planktonic foraminifera per species and station.

Station no.	<i>Globigerinita glutinata</i>		<i>Globigerinoides ruber ruber</i>		<i>Globorotalia menardii</i>	
	N	mean	N	mean	N	mean
2	120	116.4	44	149.9	110	426.3
3	134	109.9	68	120.9	20	361.8
4	79	113.6	24	124.7	18	271.7
6	33	94.1	4	119.0	3	335.3
7	163	103.1	30	108.0	3	191.0
8	295	99.4	110	109.6	37	126.7
9	134	100.1	81	95.8	48	107.0
10	764	112.4	182	108.9	567	110.7
12	259	106.3	124	101.1	221	133.6

Table A4. Results of the Kruskal–Wallis tests with Dunn–Šidák correction (DS) for the three species of studied planktonic foraminifera with the comparison groups A and B for all stations (2, 3, 4, 6, 7, 8, 9, 10, 12). Statistically significant results are highlighted with bold characters.

Group A	Group B	<i>p</i> value (DS correction)		
		<i>Globigerinita glutinata</i>	<i>Globigerinoides ruber ruber</i>	<i>Globorotalia menardii</i>
1	2	0.608080093	0.035932605	0.999999479
1	3	1	0.723194198	0.999999485
1	4	3.36203 × 10⁻⁵	0.982503452	0.99437856
1	5	0.000144447	2.75833 × 10⁻⁶	1
1	6	1.70995 × 10⁻¹⁰	0.000221489	0
1	7	1.02211 × 10⁻⁷	9.74181 × 10⁻¹¹	0
1	8	0.996222105	3.02309 × 10⁻⁹	0
1	9	0.003908006	3.43097 × 10⁻⁹	0
2	3	0.989337609	1	1
2	4	0.015508053	1	0.999997473
2	5	0.493132702	0.123828828	1
2	6	0.000252471	0.999987102	1.24834 × 10⁻⁵
2	7	0.004864475	0.001511193	1.54061 × 10⁻¹⁰
2	8	0.996326771	0.048019673	6.84652 × 10⁻¹²
2	9	0.998621508	0.032419241	0.012379879
3	4	0.00045299	1	0.999998622
3	5	0.010736135	0.225192202	1
3	6	1.88625 × 10⁻⁶	0.999910131	3.73722 × 10⁻⁵
3	7	4.49042 × 10⁻⁵	0.030466022	1.1917 × 10⁻⁹
3	8	1	0.315264384	1.36179 × 10⁻¹⁰
3	9	0.139075664	0.224002248	0.027200628
4	5	0.688875924	0.999999997	1
4	6	0.999948837	1	0.999634161
4	7	0.999983077	0.99999991	0.795884885
4	8	0.000141565	1	0.937995383
4	9	0.124403244	1	1
5	6	0.823034275	0.577023078	0.746718316
5	7	0.977102329	1	0.158783557
5	8	6.85565 × 10⁻⁵	0.99999987	0.282176207
5	9	0.999719084	1	0.99996622
6	7	1	0.021056195	0.840225369
6	8	0	0.490109341	0.992377928
6	9	0.005837358	0.348936346	0.0395251
7	8	4.3455 × 10⁻⁹	0.978892147	0.999977736
7	9	0.092684766	0.999895592	8.74673 × 10⁻⁹
8	9	0.002853583	1	0

Table A5. Results of the Kruskal–Wallis tests with Dunn–Šidák correction (DS) for the three species of studied planktonic foraminifera, with the comparison groups A and B for the depth comparison (1 represents surface, 2 represents supra-epipelagic, 3 represents epipelagic, 4 represents infra-epipelagic, and 5 represents mesopelagic, as defined in Sect. 2.3 and in Table A2). Statistically significant results are highlighted with bold characters.

Group A	Group B	<i>p</i> value (DS correction)		
		<i>Globigerinita glutinata</i>	<i>Globigerinoides ruber ruber</i>	<i>Globorotalia menardii</i>
1	2	0.999996701	0.088352274	0.977065781
1	3	0.01720279	1.19095 × 10⁻⁶	0.000614052
1	4	1.05374 × 10⁻⁵	0	1.00345 × 10⁻⁸
1	5	0.224765181	1.04835 × 10⁻⁶	0.000757423
2	3	0.016029819	0.027355658	0.102431327
2	4	0.000161843	5.92648 × 10⁻¹¹	0.000641916
2	5	0.329156978	0.000851265	0.037785271
3	4	4.55959 × 10⁻⁹	0.184506327	0.945601843
3	5	0.003616986	0.529742148	0.998132028
4	5	0.999999412	0.999981711	0.999999989




Figure A1. Example of the segmentation procedure used for the planktonic foraminifera size measurement based on tri-dimensional images generated by a Keyence digital microscope (see Sect. 2.2). **(a)** Keyence image of *Globigerinita glutinata* specimens positioned in umbilical view for a primary size segmentation based on particle elevation; **(b)** second and final size segmentation (in green) of the specimens based on an implementation of the sparse field method on the RGB data (see Sect. 2.2); at this step, the quality of each specimen size segmentation can be checked; **(c)** example of the full segmentation results on a magnified area of panel (a) with the original picture (left) and all specimens segmented in green (right).

Data availability. Planktonic foraminifera counts, species concentrations and size will be made available on request to the main author until their online publication on PANGAEA (<https://www.pangaea.de>, last access: 22 October 2021).

Author contributions. MiK and MS conceptualised the data collection. JM and MaK processed the samples and performed foraminifera shell measurements. JM did the planktonic foraminifera classification. MS performed the statistical analyses. JB provided support for the data processing (residuals and mortality) and interpretation. The manuscript was written by JM with the help of all co-authors, who approved its final version.

Competing interests. The contact author has declared that neither they nor their co-authors have any competing interests.

Disclaimer. Publisher's note: Copernicus Publications remains neutral with regard to jurisdictional claims in published maps and institutional affiliations.

Acknowledgements. The authors thank the captain, crew and participants of the RV *Meteor* expedition M140 FORAMFLUX for their assistance with plankton sampling and CTD measurements. We acknowledge the technical help provided by Sylvia Malagoli in processing some of the samples and helpful discussions with Lukas Jonkers for data visualisation. We thank the Deutsche Forschungsgemeinschaft (DFG; Deutsche Forschungsge-

meinschaft) for financing the research project of Julie Meilland and the Cluster of Excellence “The Ocean Floor – Earth’s Uncharted Interface”, whose financial support in our laboratories infrastructures contributed to the success of this research. We are also thankful to Ralf Schiebel and to the anonymous referee who provided constructive comments and helped us improve the manuscript.

Financial support. This research has been supported by the Deutsche Forschungsgemeinschaft (grant no. ME 5192/1-1).

The article processing charges for this open-access publication were covered by the University of Bremen.

Review statement. This paper was edited by Hiroshi Kitazato and reviewed by Ralf Schiebel and one anonymous referee.

References

- Almogi-Labin, A.: Population dynamics of planktic Foraminifera and Pteropoda Gulf of Aqaba, Red Sea, Proceedings of the Koninklijke Nederlandse Akademie van Wetenschappen. Series B. Palaeontology, geology, physics and chemistry, 87, 481–511, 1984.
- Anderson, O. R. and Bé, A. W.: A cytochemical fine structure study of phagotrophy in a planktonic foraminifer, *Hastigerina pelagica* (d’Orbigny), *Biol. Bull.*, 151, 437–449, 1976.
- Babcock, R., Bull, G., Harrison, P. L., Heyward, A., Oliver, J., Wallace, C., and Willis, B.: Synchronous spawnings of 105 scleractinian coral species on the Great Barrier Reef, *Mar. Biol.*, 90, 379–394, 1986.
- Bé, A., Hemleben, C., Anderson, O., and Spindler, M.: Pore structures in planktonic foraminifera, *J. Foramin. Res.*, 10, 117–128, 1980.
- Bé, A. W.: Quantitative multiple opening-and-closing plankton samplers, *Deep Sea Research and Oceanographic Abstracts*, 9, 144–151, 1962.
- Bé, A. W. and Hemleben, C.: Calcification in a living planktonic foraminifer, *Globigerinoides sacculifer* (Brady), *Neues Jahrb. Geol. Paläontol.*, 134, 221–234, 1970.
- Bé, A. W., Hemleben, C., Anderson, O. R., Spindler, M., Hacunda, J., and Tuntivate-Choy, S.: Laboratory and field observations of living planktonic foraminifera, *Micropaleontol.*, 23, 155–179, 1977.
- Berger, W., Killingley, J., and Vincent, E.: Sable isotopes in deep-sea carbonates-box core erdc-92, west equatorial pacific, *Oceanol. Acta*, 1, 203–216, 1978.
- Bijma, J. and Hemleben, C.: Population dynamics of the planktic foraminifer *Globigerinoides sacculifer* (Brady) from the central Red Sea, *Deep-Sea Res. Pt. I*, 41, 485–510, 1994.
- Bijma, J., Erez, J., and Hemleben, C.: Lunar and semi-lunar reproductive cycles in some spinose planktonic foraminifers, *J. Foramin. Res.*, 20, 117–127, 1990.
- Boyd, C. and Gradmann, D.: Impact of osmolytes on buoyancy of marine phytoplankton, *Mar. Biol.*, 141, 605–618, 2002.
- Brawley, S. H. and Johnson, L. E.: Gametogenesis, gametes and zygotes: an ecological perspective on sexual reproduction in the algae, *Brit. Phycol. J.*, 27, 233–252, 1992.
- Brummer, G.-J. A., Hemleben, C., and Spindler, M.: Planktonic foraminiferal ontogeny and new perspectives for micropalaeontology, *Nature*, 319, 50–52, 1986.
- Brummer, G. J. A. and Kroon, D.: Planktonic foraminifers as tracers of ocean-climate history: Ontogeny, relationships and preservation of modern species and stable isotopes, phenotypes and assemblage distribution in different water masses, Free University Press, Amsterdam, 1988.
- Caron, D. A., Faber, W. W., and Bé, A. W.: Growth of the spinose planktonic foraminifer *Orbulina universa* in laboratory culture and the effect of temperature on life processes, *J. Mar. Biol. Assoc. UK*, 67, 343–358, 1987.
- Chernihovsky, N., Almogi-Labin, A., Kienast, S., and Torfstein, A.: The daily resolved temperature dependence and structure of planktonic foraminifera blooms, *Sci. Rep.-UK*, 10, 1–12, 2020.
- Clifton, K. E.: Mass spawning by green algae on coral reefs, *Science*, 275, 1116–1118, 1997.
- Davis, C. V., Livsey, C. M., Palmer, H. M., Hull, P. M., Thomas, E., Hill, T. M., and Benitez-Nelson, C. R.: Extensive morphological variability in asexually produced planktic foraminifera, *Sci. Adv.*, 6, eabb8930, <https://doi.org/10.1126/sciadv.abb8930>, 2020.
- Erez, J.: The source of ions for biomineralization in foraminifera and their implications for paleoceanographic proxies, *Rev. Mineral. Geochem.*, 54, 115–149, 2003.
- Erez, J., Almogi-Labin, A., and Avraham, S.: On the life history of planktonic foraminifera: lunar reproduction cycle in *Globigerinoides sacculifer* (Brady), *Paleoceanography*, 6, 295–306, 1991.
- Fairbanks, R. G., Sverdrlove, M., Free, R., Wiebe, P. H., and Bé, A. W.: Vertical distribution and isotopic fractionation of living planktonic foraminifera from the Panama Basin, *Nature*, 298, 841–844, 1982.
- Fieux, M.: 4 Surface and subsurface circulation, in: *The planetary ocean*, EDP Sciences, Les Ulis, 219–252, 2021.
- Greco, M., Jonkers, L., Kretschmer, K., Bijma, J., and Kucera, M.: Depth habitat of the planktonic foraminifera *Neoglobobulimina pacyhyderma* in the northern high latitudes explained by sea-ice and chlorophyll concentrations, *Biogeosciences*, 16, 3425–3437, <https://doi.org/10.5194/bg-16-3425-2019>, 2019.
- Groeneveld, J., Ho, S. L., Mackensen, A., Mohtadi, M., and Laepple, T.: Deciphering the variability in Mg/Ca and stable oxygen isotopes of individual foraminifera, *Paleoceanogr. Paleocl.*, 34, 755–773, 2019.
- Haarmann, T., Hathorne, E. C., Mohtadi, M., Groeneveld, J., Kölling, M., and Bickert, T.: Mg/Ca ratios of single planktonic foraminifer shells and the potential to reconstruct the thermal seasonality of the water column, *Paleoceanography*, 26, PA3218, <https://doi.org/10.1029/2010PA002091>, 2011.
- Hemleben, C. and Bijma, J.: Foraminiferal population dynamics and stable carbon isotopes, in: *Carbon cycling in the glacial ocean: Constraints on the ocean’s role in global change*, Springer, Berlin, Heidelberg, 145–166, 1994.
- Hemleben, C., Spindler, M., Breiting, I., and Deuser, W. G.: Field and laboratory studies on the ontogeny and ecology of some globorotaliid species from the Sargasso Sea off Bermuda, *J. Foramin. Res.*, 15, 254–272, 1985.

- Hemleben, C., Spindler, M., and Anderson, O. R.: Modern planktonic Foraminifera, Springer, Berlin, 1989.
- Iwasaki, S., Kimoto, K., Kuroyanagi, A., and Kawahata, H.: Horizontal and vertical distributions of planktic foraminifera in the subarctic Pacific, *Mar. Micropaleontol.*, 130, 1–14, 2017.
- Iwasaki, S., Kimoto, K., Sasaki, O., Kano, H., and Uchida, H.: Sensitivity of planktic foraminiferal test bulk density to ocean acidification, *Sci. Rep.-UK*, 9, 1–9, 2019.
- Jentzen, A., Schönfeld, J., Weiner, A. K. M., Weinkauff, M. F. G., Nürnberg, D., and Kučera, M.: Seasonal and interannual variability in population dynamics of planktic foraminifera off Puerto Rico (Caribbean Sea), *J. Micropalaeontol.*, 38, 231–247, <https://doi.org/10.5194/jm-38-231-2019>, 2019.
- Jonkers, L., Reynolds, C. E., Richey, J., and Hall, I. R.: Lunar periodicity in the shell flux of planktonic foraminifera in the Gulf of Mexico, *Biogeosciences*, 12, 3061–3070, <https://doi.org/10.5194/bg-12-3061-2015>, 2015.
- Kawahata, H., Nishimura, A., and Gagan, M. K.: Seasonal change in foraminiferal production in the western equatorial Pacific warm pool: evidence from sediment trap experiments, *Deep-Sea Res. Pt. II*, 49, 2783–2800, 2002.
- Kučera, M., Siccha, M., Morard, R., Jonkers, L., Schmidt, C., Munz, P., Groeneveld, J., Fischer, G., Ruhland, G., and Klann, M.: Scales of Population Dynamics, Ecology and Diversity of Planktonic Foraminifera and their Relationship to Particle Flux in the Eastern Tropical Atlantic: Cruise No. M140, 11.8. 2017–5.9. 2017, Mindelo (Cabo Verde) – Las Palmas (Spain) – FORAM-FLUX, DFG-Senatskommission für Ozeanographie, Bremen, 2019.
- Lankton, S.: Sparse field methods-technical report, Georgia institute of technology, Atlanta, 2009.
- Lessa, D., Morard, R., Jonkers, L., Venancio, I. M., Reuter, R., Baumeister, A., Albuquerque, A. L., and Kucera, M.: Distribution of planktonic foraminifera in the subtropical South Atlantic: depth hierarchy of controlling factors, *Biogeosciences*, 17, 4313–4342, <https://doi.org/10.5194/bg-17-4313-2020>, 2020.
- Lin, H.-L.: The seasonal succession of modern planktonic foraminifera: Sediment traps observations from southwest Taiwan waters, *Cont. Shelf Res.*, 84, 13–22, 2014.
- Lončarić, N., Brummer, G.-J. A., and Kroon, D.: Lunar cycles and seasonal variations in deposition fluxes of planktic foraminiferal shell carbonate to the deep South Atlantic (central Walvis Ridge), *Deep-Sea Res. Pt. I*, 52, 1178–1188, 2005.
- MATLAB: MATLAB. 9.3.0.713579 (R2017b), Natick, Massachusetts, The MathWorks Inc., 2017.
- Meilland, J., Siccha, M., Weinkauff, M. F., Jonkers, L., Morard, R., Baranowski, U., Baumeister, A., Bertlich, J., Brummer, G.-J., and Debray, P.: Highly replicated sampling reveals no diurnal vertical migration but stable species-specific vertical habitats in planktonic foraminifera, *J. Plankton Res.*, 41, 127–141, 2019.
- Mohiuddin, M. M., Nishimura, A., Tanaka, Y., and Shimamoto, A.: Seasonality of biogenic particle and planktonic foraminifera fluxes: response to hydrographic variability in the Kuroshio Extension, northwestern Pacific Ocean, *Deep-Sea Res. Pt. I*, 51, 1659–1683, 2004.
- Morard, R., Füllberg, A., Brummer, G.-J. A., Greco, M., Jonkers, L., Wizemann, A., Weiner, A. K., Darling, K., Siccha, M., and Ledevin, R.: Genetic and morphological divergence in the warm-water planktonic foraminifera genus Globigerinoides, *PLoS one*, 14, e0225246, <https://doi.org/10.1371/journal.pone.0225246>, 2019.
- Murray, J.: Ecology and paleoecology of benthic Foraminifera, Longman Scientific & Technical, Essex, 1991.
- Ofstad, S., Zamelczyk, K., Kimoto, K., Chierici, M., Fransson, A., and Rasmussen, T. L.: Shell density of planktonic foraminifera and pteropod species *Limacina helicina* in the Barents Sea: Relation to ontogeny and water chemistry, *PLoS One*, 16, e0249178, <https://doi.org/10.1371/journal.pone.0249178>, 2021.
- Peeters, F. J. and Brummer, G.-J. A.: The seasonal and vertical distribution of living planktic foraminifera in the NW Arabian Sea, *Geol. Soc. Lond. Spec. Publ.*, 195, 463–497, 2002.
- Pracht, H., Metcalfe, B., and Peeters, F. J. C.: Oxygen isotope composition of the final chamber of planktic foraminifera provides evidence of vertical migration and depth-integrated growth, *Biogeosciences*, 16, 643–661, <https://doi.org/10.5194/bg-16-643-2019>, 2019.
- Rebotim, A., Voelker, A. H. L., Jonkers, L., Waniek, J. J., Meggers, H., Schiebel, R., Fraile, I., Schulz, M., and Kucera, M.: Factors controlling the depth habitat of planktonic foraminifera in the subtropical eastern North Atlantic, *Biogeosciences*, 14, 827–859, <https://doi.org/10.5194/bg-14-827-2017>, 2017.
- Rhumbler, L.: Die Foraminiferen (Thalamophoren) der Plankton Expedition, Pt. 1, Die Allgemeinen Organisationsverhältnisse der Foraminifera, Lipsius & Tischer, Kiel und Leipzig, 331 pp., 1911.
- Salmon, K. H., Anand, P., Sexton, P. F., and Conte, M.: Upper ocean mixing controls the seasonality of planktonic foraminifer fluxes and associated strength of the carbonate pump in the oligotrophic North Atlantic, *Biogeosciences*, 12, 223–235, <https://doi.org/10.5194/bg-12-223-2015>, 2015.
- Schiebel, R.: Planktic foraminiferal sedimentation and the marine calcite budget, *Global Biogeochem. Cy.*, 16, 3–1–3–21, 2002.
- Schiebel, R. and Hemleben, C.: Modern planktic foraminifera, *Paläontol. Z.*, 79, 135–148, 2005.
- Schiebel, R. and Hemleben, C.: Planktic foraminifera in the modern ocean, Springer, Berlin, Heidelberg, 2017.
- Schiebel, R., Bijma, J., and Hemleben, C.: Population dynamics of the planktic foraminifer *Globigerina bulloides* from the eastern North Atlantic, *Deep-Sea Res. Pt. I*, 44, 1701–1713, 1997.
- Schiffelbein, P. and Hills, S.: Direct assessment of stable isotope variability in planktonic foraminifera populations, *Palaeogeogr. Palaeoclimatol.*, 48, 197–213, 1984.
- Schlitzer, R.: Ocean Data View, available at: <https://odv.awi.de> (last access: 22 October 2021), 2015.
- Siccha, M., Schiebel, R., Schmidt, S., and Howa, H.: Short-term and small-scale variability in planktic foraminifera test flux in the Bay of Biscay, *Deep-Sea Res. Pt. I*, 64, 146–156, 2012.
- Spero, H. J., Eggins, S. M., Russell, A. D., Vetter, L., Kilburn, M. R., and Hönisch, B.: Timing and mechanism for intratest Mg/Ca variability in a living planktic foraminifer, *Earth Planet. Sc. Lett.*, 409, 32–42, 2015.
- Spindler, M., Anderson, O., Hemleben, C., and Bé, A.: Light and electron microscopic observations of gametogenesis in *Hastigerina pelagica* (Foraminifera), *J. Protozool.*, 25, 427–433, 1978.
- Spindler, M., Hemleben, C., Bayer, U., Bé, A., and Anderson, O.: Lunar periodicity of reproduction in the planktonic foraminifer *Hastigerina pelagica*, *Mar. Ecol.-Prog. Ser.*, 1, 61–64, 1979.

- Stangeew, E.: Distribution and Isotopic Composition of Living Planktonic Foraminifera *N. pachyderma* (sinistral) and *T. quinqueloba* in the High Latitude North Atlantic, Christian-Albrechts Universität Kiel, 2001.
- Steinhardt, J., de Nooijer, L. L., Brummer, G. J., and Reichert, G. J.: Profiling planktonic foraminiferal crust formation, *Geochem. Geophys. Geosy.*, 16, 2409–2430, 2015.
- Stuut, J.-B., Brummer, G.-J., Korte, L., and van der Does, M.: Present-day Saharan dust deposition in the Atlantic Ocean and its marine-environmental consequences, *Geophys. Res. Abstr.*, EGU2019-12545, EGU General Assembly 2019, Vienna, Austria, 2019.
- Takagi, H., Moriya, K., Ishimura, T., Suzuki, A., Kawahata, H., and Hirano, H.: Individual migration pathways of modern planktonic foraminifers: Chamber-by-chamber assessment of stable isotopes, *Paleontol. Res.*, 20, 268–284, 2016.
- Takagi, H., Kimoto, K., Fujiki, T., Saito, H., Schmidt, C., Kucera, M., and Moriya, K.: Characterizing photosymbiosis in modern planktonic foraminifera, *Biogeosciences*, 16, 3377–3396, <https://doi.org/10.5194/bg-16-3377-2019>, 2019.
- Takagi, H., Kurasawa, A., and Kimoto, K.: Observation of asexual reproduction with symbiont transmission in planktonic foraminifera, *J. Plankton Res.*, 42, 403–410, 2020.
- Takahashi, K. and Bé, A. W. H.: Planktonic foraminifera: factors controlling sinking speeds, *Deep-Sea Res. Pt. A*, 31, 1477–1500, 1984.
- Venancio, I. M., Franco, D., Belem, A. L., Mulitza, S., Siccha, M., Albuquerque, A. L. S., Schulz, M., and Kucera, M.: Planktonic foraminifera shell fluxes from a weekly resolved sediment trap record in the southwestern Atlantic: Evidence for synchronized reproduction, *Mar. Micropaleontol.*, 125, 25–35, 2016.
- Volkman, R.: Planktonic foraminifers in the outer Laptev Sea and the Fram Strait – Modern distribution and ecology, *J. Foramin. Res.*, 30, 157–176, 2000.
- Weinkauff, M. F., Siccha, M., and Weiner, A. K.: Reproduction of a marine planktonic protist: Individual success versus population survival, *bioRxiv*, <https://doi.org/10.1101/2020.11.04.368100>, 2020.
- Žuljević, A. and Antolić, B.: Synchronous release of male gametes of *Caulerpa taxifolia* (Caulerpales, Chlorophyta) in the Mediterranean Sea, *Phycologia*, 39, 157–159, 2000.